BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2022-23/OW/WORK_INDENT53733

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/16/2022-23, Date: 12-10-2022

Name of Work: Maintenance of water supply Existing borewells at Chokkanahalli, Thirumenahalli Surrounding area in Ward No. 06 Kogilu.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of S Narayana Rao ( )	
				In Figures	In Words
1	90	The lifting of submergible pumpset from well	Each	1106.17	Rupees One Thousand One Hundred Six and Seventeen Paise Only
2	45	The Transportation of pumping machineries	Each	944.55	Rupees Nine Hundred Forty Four and Fifty Five Paise Only
3	5	Rewinding of submergible pumpset with copper winding wires of appropriate guage, as per specifications and / or directions of the departmental officials, including all materials, labour, equipment and testing. for all types of submergible pumpsets etc.(with guarantee period not less than 6 months). For all types of submergible pumpsets above 7.0 HP and upto 7.5H.P.	Each	4029.03	Rupees Four Thousand Twenty Nine and Three Paise Only
4	10	Rewinding of submergible pumpset with copper winding wires of appropriate guage, as per specifications and / or directions of the departmental officials, including all materials, labour, equipment and testing. for all types of submergible pumpsets etc.(with guarantee period not less than 6 months). For all types of submergible pumpsets above 10 HP and upto 11 H.P.	Each	5421.27	Rupees Five Thousand Four Hundred Twenty One and Twenty Seven Paise Only
5	15	Rewinding of submergible pumpset with copper winding wires of appropriate guage, as per specifications and / or directions of the departmental officials, including all materials, labour, equipment and testing. for all types of submergible pumpsets etc.(with guarantee period not less than 6 months). For all types of submergible pumpsets above 12 HP and upto 13 H.P.	Each	6279.16	Rupees Six Thousand Two Hundred Seventy Nine and Sixteen Paise Only
6	15	Rewinding of submergible pumpset with copper winding wires of appropriate guage, as per specifications and / or directions of the departmental officials, including all materials, labour, equipment and testing. for all types of submergible pumpsets etc.(with guarantee period not less than 6 months). For all types of submergible pumpsets 15HP to 20 HP	Each	9372.04	Rupees Nine Thousand Three Hundred Seventy Two and Four Paise Only
7	90	Pump bowls of same type and make	Nos	686.37	Rupees Six Hundred Eighty Six and Thirty Seven Paise Only
8	25	Intermediate Piece (I.P) With IP Leaded Bronxe bush	Nos	774.53	Rupees Seven Hundred Seventy Four and Fifty Three Paise Only
9	30	Upper Flange	Nos	282.32	Rupees Two Hundred Eighty Two and Thirty Two Paise Only
10	30	Upper/ Lower Housing	Nos	664.33	Rupees Six Hundred Sixty Four and Thirty Three Paise Only
11	50	Guide vane	Nos	398.81	Rupees Three Hundred Ninety Eight and Eighty One Paise Only
12	35	Impeller Shell moulded with aluminium Bronze)	Nos	608.71	Rupees Six Hundred Eight and Seventy One Paise Only
13	30	Discharge outlet (D.O) Bearing D.O Steel Bush	Nos	718.91	Rupees Seven Hundred Eighteen and Ninety One Paise Only
14	45	Pump shaft made out of stainless steel Centreless ground with key way (upto 8 stages)	Nos	1273.04	Rupees One Thousand Two Hundred Seventy Three and Four Paise Only
15	35	Pump Couping (Stainless Steel)	Nos	1273.04	Rupees One Thousand Two Hundred Seventy Three and Four Paise Only
16	100	Stud and Nuts	Each	99.7	Rupees Ninety Nine and Seventy Paise Only
17	25	Motor Base With Pin	Each	509.01	Rupees Five Hundred Nine and One Paise Only

ಸಹಾಯಕ ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ ಯಲಹಂಕ ವಲಯ
ಯಲಹಂಕ ಉಪನಗರ ಮಹಾನಗರ ಪಾಲಿಕೆ ಬೆಂಗಳೂರು-560092.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of S Narayana Rao ( )	
				In Figures	In Words
18	45	The Starter of Motor up to 4 to 5 HP	Nos	5864.61	Rupees Five Thousand Eight Hundred Sixty Four and Sixty One Paise Only
19	45	The Rotor of Motor up to 4 to 5 HP	Nos	5090.08	Rupees Five Thousand Ninety and Eight Paise Only
20	40	Carbon Housing	Nos	830.15	Rupees Eight Hundred Thirty and Fifteen Paise Only
21	40	Thrust bearing block assembly complete with Segment bearing pad.up to 4 to 5 HP	Nos	995.98	Rupees Nine Hundred Ninety Five and Ninety Eight Paise Only
22	35	Oil Seal	Nos	177.37	Rupees One Hundred Seventy Seven and Thirty Seven Paise Only
23	45	Oil Seal Steel Bush	Nos	177.37	Rupees One Hundred Seventy Seven and Thirty Seven Paise Only
24	100	Steel Bush	Nos	221.44	Rupees Two Hundred Twenty One and Forty Four Paise Only
25	100	Allen Screw	Nos	718.91	Rupees Seven Hundred Eighteen and Ninety One Paise Only
26	35	Pump Key (Stainless Steel)	Nos	277.07	Rupees Two Hundred Seventy Seven and Seven Paise Only
27	30	Non – return valve (NRV) assembly complete with rubber 'O' Ring	Nos	608.71	Rupees Six Hundred Eight and Seventy One Paise Only
28	45	Cable Guard	Nos	907.82	Rupees Nine Hundred Seven and Eighty Two Paise Only
29	40	Strainer	Nos	331.64	Rupees Three Hundred Thirty One and Sixty Four Paise Only
30	35	Brass Filter	Nos	497.46	Rupees Four Hundred Ninety Seven and Forty Six Paise Only
31	45	Re-erection charges of pumping machineries including overhauling and pointing	Each	1493.44	Rupees One Thousand Four Hundred Ninety Three and Forty Four Paise Only
32	35	Lock Ring	Each	133.29	Rupees One Hundred Thirty Three and Twenty Nine Paise Only
33	35	Top Carbon/Ferrodo padding	Each	1029.56	Rupees One Thousand Twenty Nine and Fifty Six Paise Only
34	35	Bearing (Gunmetal) Centrifugal) Cast Aluminium Bronxe, Beaing bush	Each	497.46	Rupees Four Hundred Ninety Seven and Forty Six Paise Only
35	35	Circillps	Each	66.12	Rupees Sixty Six and Twelve Paise Only
36	96	Supplying and fixing of Porcelain fuse channel with cut out on existing wooden / panel using necessary nuts, bolts and washer etc.,63 Amps	Nos	157.43	Rupees One Hundred Fifty Seven and Forty Three Paise Only
37	750	Cutting and threading G.I. pipes for pump fitting, public fountains with appurtenances., where the length of pipe laid is less than 6 metre Pipes of dia 32mm to 80mm	Each	90.26	Rupees Ninety and Twenty Six Paise Only
38	1085	Supply and delivery at site Brand new best make PVC insulated cable of Flat 3 core (sheathed) of nominal cross sectional area as per IS 694-1990 with ISI Mark and as per its latest amendments. 1x3x6 m2	Mtr	220.4	Rupees Two Hundred Twenty and Forty Paise Only

ಕಾರ್ಯ ಪಾಲಕ ಅಭಿಯಂತರರು
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ ಬೆಂಗಳೂರು-560002.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of S Narayana Rao ( )	
				In Figures	In Words
39	20	Supply and delivery at site delivery of best indigenous brand new MCB (Miniature Circuit Breakers) of required capacity as per IS 88228/1978 and its latest amendments and with ISI Mark of 6/10/16/20/25/40 Amps with scalable box	Nos	1331.88	Rupees One Thousand Three Hundred Thirty One and Eighty Eight Paise Only
40	169	Earth work excavation for pipeline trenches in all kinds of soils by mechanical means above 600 mm trench width as per drawing and technical specifications, including setting out, construction of shoring, strutting, barricading, caution lights, bracing, using sight rails & boning rods at every 100 mm whevere necessary as directed, removal of stumps and other deleterious matter, dressing of sides and levelling the bottom of trench to the extent required , utilising the available excavated earth locally for the work etc., and all other appurtenances complete in the following strata. Depth exceeding 1.5 m, but not exceeding 3 m	Cum	542.59	Rupees Five Hundred Forty Two and Fifty Nine Paise Only
41	500	Providing and installing at site of work P.V.C. pipes including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour charges and all lift charges, handling charges including encasing the pipe around to a depth not less than 15 cms with gravel or selected earth available from the excavation etc. 75mm(weight of pipe -0.917 kg)	Mtr	215.0	Rupees Two Hundred Fifteen Only
42	169	Refilling available earth around trenches/pipelines, cables in layers not exceeding 20 cms in depth, compacting each deposited layer by ramming after watering with a lead upto 50 m , and lift upto 1.5 m. ncluding cost of all labour complete as per specifications	Cum	137.0	Rupees One Hundred Thirty Seven Only

Signature of the Contractor

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92